Gerd

Additional information please contact:

Borr Drilling Limited E. Pearman Building, 2nd Floor 9 Par-la-Ville Road. Hamilton HM11. Bermuda

marketing@borrdrilling.com - www.borrdrilling.com

High Specification Jackup

General Description	
Design / Generation	PPL Pacific Class 400
Constructing Shipyard	PPL Shipyard PTE Ltd., Singapore
Year Entered Service / Significant	Upgrades 2018
Classification	ABS-A1, Self-Elevating Drilling Unit
Flag	Vanuatu
Overall Dimensions	236.5 ft. Long x 224.4 ft. Wide x 27.9 ft deep
Legs	(3) 533 ft. long, Triangular
Drafts	19.50 ft at load line
Accommodation	150 persons
Displacement	43,840 kips
Variable Deck 7,498	kips operating / 5,000 kips transit (spud cans full)
Transit Speed	up to 5 knots, @ 150st bollard pull
Operating Water Depth	
Maximum Drilling Depth	30,000ft

Drilling Equipment

Derrick NOV Derrick 160ft. high, with 35ft. x 35ft. base

Hookload Capacity 1,500,000lbs gross nominal capacity

Cantilever/ Drill floor

75 ft / 15 ft Port & 15 ft Stbd **Drawworks** NOV ADS-10T driven by (3) Baylor electric motors. Rated to

750st with 14 lines of 1-5/8" drill line

Rotary Table National Oilwell D-495 49-1/2" with a rated capacity of

750st

Top Drive NOV TDS-8SA Hoisting cap: 750 s-ton, AC motor: 1150 hp,

intermittent torque: 95,000 ft-lbs., maximum drilling torque: 62,250 ft- lbs., maximum speed 270 rpm, (2) IBOP 3 1/6" -

15k Psi

(1) NOV ST120 Iron Roughneck. 3 1/2" to 10" tubulars. Make up torque 100000 ft/lbs., Break-out torque 120000 Tubular Handling

ft/lbs. Spinning speed 80 RPM (with 5 "OD) spinning torque

3000 ft/lbs.

(3) NOV 14-P-220 triplex pumps (9 inch bore and 14 inch Mud Pumps

stroke), each driven by 1,150 hp (NOV Baylor AC motor)

7,500 psi rated

HP Mud System Rated for 7,500psi

Solids Control (5) NOV Brandt VSM 300 shale shakers. Mud cleaner installed

over one shale shaker.

Power & Machinery

Main Power (5) Caterpillar 3516C-HD diesel engines rated at 2,150hp at 1200rpm each with Kato generator rated to 2,150KVA

(1) Caterpillar 3508B DITA diesel engine rated at 1,428hp at **Emergency Power**

1,800rpm with Leroy Somer generator rated to 1020KVA

Storage Capacities

Bulk Material(mud + cement) 11,653 cu-ft

BOP & Well Control Equipment

BOP Rams (2) Cameron double rams 18-3/4" 15k psi BOP **BOP Annular** (1) Cameron 18-3/4" 10,000psi annular preventer

BOP Handling (4) J D Neuhaus EH-75 BOP main hoists, rated 75mt each Diverter Vetco KFDJ 500, 49-1/2" diverter rated to 500psi with (2) 16" flow line, (2) 12" overboard, (1) 6" deluge and (1) 3" fill line

Mooring Equipment

Mooring Winches (4) Mentrade electric winches rated at 31.75 st

capacity 118st brake holding

Anchor Lines 3000ft x 1-1/2" galvanized wire rope

(4) Flipper Delta anchor Anchors

Cranes

(3) Baker Marine cranes, 50mt capacity. 2 Cranes with118ft boom, 1 crane with 108ft boom Cranes

Special Features & Other Information

Primary - TSC 225mt Vertical Load and 26mt Lateral Load -CTU hydraulic driven @ 4.66 m and 10.66 m from AFT transom

Secondary - Claxton 100 T tensioner system 220mt tension

capacity. 2 lift points, 48" stroke

RPD System

Rated for Sikorsky S-61 and S-92 helicopters. CAP 437 Helideck

Offline Systems:

(1) NOV-ST100 Iron Roughneck. 3 1/2" to 9-3/4" tubulars Iron Roughneck

NOV Dreco racking platform capacities: Up to 238 stands Pipe Handling (Driller Side) + 176 stands (Offline Racking Board) 5-7/8" DP.4

stands 9-1/2" DC + 8 stands 8" DC 155 stands 7" casing + 22

stands 9-5/8" casing.

OAC (Offline Activity Crane) Forum 10mt derrick mounted OA Crane

for offline pipe handling



These specifications are intended for general reference purposes only, as actual equipment and specifications may vary based upon subsequent changes, the contract situation and customer needs. All equipment shall be operated and maintained at all times, in compliance with Borr Drilling standard operating manuals, policies and procedures, and within its stated operational limits or continuous rated capacity, in order to assure maximum operational efficiency.



